

# RIG #10



## DRAWWORKS

- Ideco 1200UE 1000 HP

## TRAVELING BLOCK

- National 500 Ton

## TOP DRIVE

- Canrig 275 Ton

## B.O.P EQUIPMENT

- B.O.P – 11" 5M Double & Single Gate, 11" 5M
- Annular CLOSING UNIT - 160 Gallon 8 Station
- CHOKE MANIFOLD - 3" 5M Or As Needed

## MUD SYSTEM

- MUD PUMP #1 - FB-1600 (5M)
- MUD PUMP #2 - FB-1600 (5M)
- MUD TANKS – 800 BBL
- SHALE SHAKER – Dual NOV King Cobra

## STORAGE CAPACITIES

- WATER TANKS - 400 BBL

## POWER PACKAGE AND LIGHTING

- SCR - Omron PLC System w/ 3 x 3 Top Drive Feeder
- ENGINES - (3) MTU V16 2000

## MAST AND SUBSTRUCTURE

- MAST – 142' x 21' w/768,000# Hook
- SUBSTRUCTURE - Superior Box on Box  
20'Hx36'x25'
- HIGH DENSITY SELF MOVING PACKAGE – 135'  
Center of Well

## AUXILIARY EQUIPMENT

- GAS BUSTER ATMOSPHERIC
- BOILER - 150 HP
- PUSHER HOUSE - 13' X 55' Atco

## TUBULARS & HANDLING

- MECHANICAL ROUGHNECK – B&V 80
- POWER CATWALK – Power Cat 3000
- DRILL PIPE - 5" Or As Needed
- DRILL COLLARS – 6 3/4" Or As Needed Per  
Specifications

## DRILLING EQUIPMENT

- AUTO DRILLER - As Per Contract

## DATA ACQUISITION

- RECORDER - EDR