

DRAWWORKS

•Skytop Brewster N-95E 1500 HP

TRAVELING BLOCK

•400 TON

TOP DRIVE

•Canrig 275 Ton 6027 AC

B.O.P EQUIPMENT

•B.O.P – 11" 5M •CLOSING UNIT - 120 Gallon Hydril 5 Station •CHOKE MANIFOLD - 3" 5M Or As Needed

MUD SYSTEM

•MUD PUMP #1 - FB-1600 •MUD PUMP #2 - FB-1600 •MUD TANKS – 800 BBL •SHALE SHAKER – Dual NOV King Cobra

STORAGE CAPACITIES

•WATER TANKS - 400 BBL

POWER PACKAGE AND LIGHTING

•SCR - Omron PLC System w/ 3 x 3 Top Drive Feeder •ENGINES - (3) Cat 3512A

MAST AND SUBSTRUCTURE

•MAST – 142' x 21' w/768,000# Hook

- •SUBSTRUCTURE Sky Top Box on Box 21'Hx30'
- •HIGH DENSITY SELF MOVING PACKAGE 135' Center of Well

AUXILIARY EQUIPMENT

•GAS BUSTER ATMOSPHERIC

- •BOILER 150 HP
- •PUSHER HOUSE 13' X 55' Atco

TUBULARS & HANDLING

- •MECHNICAL ROUGHNECK
- •POWER CATWALK As Needed
- •DRILL PIPE 5" Or As Needed
- •DRILL COLLARS 6 3/4" Or As Needed

DRILLING EQUIPMENT

•AUTO DRILLER - As Per Contract

DATA ACQUISITION

•RECORDER - EDR

Cyclone Drilling Inc.

Gillette, WY