

RIG #30



DRAWWORKS

- Skytop Brewster N-12E 1500 HP

TRAVELING BLOCK

- Continental Emsco 500 Ton

TOP DRIVE

- Canrig 275 Ton

B.O.P EQUIPMENT

- B.O.P – 11" 5M Double Gate, 11" 5M Annular
- CLOSING UNIT - 160
- CHOKE MANIFOLD - 3" x 2" 5M Or As Needed

MUD SYSTEM

- MUD PUMP #1 – T-1600 (5M)
- MUD PUMP #2 – T-1600 (5M)
- MUD TANKS – 800 BBL
- SHALE SHAKER – (2) Dual King Cobra
Linear Shakers

STORAGE CAPACITIES

- WATER TANKS - 400 BBL

POWER PACKAGE AND LIGHTING

- SCR - Omron PLC System
- ENGINES - (3) MTU V16 2000

MAST AND SUBSTRUCTURE

- MAST – 142' x 21' w/768,000# Hook
- SUBSTRUCTURE – W&W Rigs Box on Box
20'Hx36'x25'
- HIGH DENSITY SELF MOVING PACKAGE – 135'
Center of Well

AUXILIARY EQUIPMENT

- GAS BUSTER ATMOSPHERIC
- BOILER - 150 HP
- PUSHER HOUSE - 14' X 48' Ameri-Tech

TUBULARS & HANDLING

- MECHANICAL ROUGHNECK – B&V 80
- POWER CATWALK – Power Cat 3000
- DRILL PIPE – 4 1/2" Or As Needed
- DRILL COLLARS – 6 3/4" Or As Needed

DRILLING EQUIPMENT

- AUTO DRILLER - As Per Contract

DATA ACQUISITION

- RECORDER - EDR