

RIG #33



DRAWWORKS

- Commander 1500 HP AC

TRAVELING BLOCK

- National 500 Ton

TOP DRIVE

- Canrig 275 Ton

B.O.P EQUIPMENT

- B.O.P W/ HANDLING SYSTEM- As Per Contract
- CLOSING UNIT – 220 Gallon 6 Station
- CHOKE MANIFOLD – As Per Contract

MUD SYSTEM

- MUD PUMP #1 – FB-1600 (7.5M)
- MUD PUMP #2 – FB-1600 (7.5M)
- MUD TANKS – 800 BBL
- SHALE SHAKER – (2) Dual King Cobra

STORAGE CAPACITIES

- WATER TANKS - 400 BBL

POWER PACKAGE AND LIGHTING

- VFD – Canrig VFD
- ENGINES - (3) MTU V16 2000

MAST AND SUBSTRUCTURE

- MAST – 142' x 25' w/787,000# Hook
- SUBSTRUCTURE – Box on Box 20'Hx33'x48'
- HIGH DENSITY SELF MOVING PACKAGE – 135' Center of Well

AUXILIARY EQUIPMENT

- GAS BUSTER ATMOSPHERIC
- BOILER - 150 HP
- PUSHER HOUSE - 13' X 55' Atco
- DRYING SHAKER TANK – NOV Cobra
- FLARE TANK – Cyclone Design

TUBULARS & HANDLING

- MECHANICAL ROUGHNECK – B&V 80
- POWER CATWALK – Canrig Power Cat 3000
- DRILL PIPE –5" Or As Needed
- DRILL COLLARS – 6 3/4" Or As Needed

DRILLING EQUIPMENT

- AUTO DRILLER – Canrig DrillSmart

DATA ACQUISITION

- RECORDER - EDR