

# RIG #34



## DRAWWORKS

- Canrig Commander 2000AC

## TRAVELING BLOCK

- National 500 Ton

## TOP DRIVE

- Canrig 500 Ton

## B.O.P EQUIPMENT

- B.O.P – As per Contract
- CLOSING UNIT - 160 Gallo
- CHOKE MANIFOLD - As per Contract

## MUD SYSTEM

- MUD PUMP #1 - FB-1600 (5M)
- MUD PUMP #2 - FB-1600 (5M)
- MUD PUMP #2 - FB-1600 (5M)
- MUD TANKS – 800 BBL
- SHALE SHAKER – (3) Swaco Mongoose Pro

## STORAGE CAPACITIES

- WATER TANKS - 400 BBL

## POWER PACKAGE AND LIGHTING

- VFD - Canrig VFG
- ENGINES - (3) MTU 16V 2000 (1500 HP)

## MAST AND SUBSTRUCTURE

- MAST – 142' x 25' w/ 1,000,000# Hook
- SUBSTRUCTURE – Superior Box on Box 26'Hx36'
- HIGH DENSITY SELF MOVING PACKAGE – 150' Center of Well

## AUXILIARY EQUIPMENT

- GAS BUSTER ATMOSPHERIC
- BOILER - 150 HP
- PUSHER HOUSE - 12' X 48' Alta-Fab

## TUBULARS & HANDLING

- MECHANICAL ROUGHNECK – B&V 80
- POWER CATWALK – Power Cat 3000
- DRILL PIPE - 5" Or As Needed
- DRILL COLLARS – 6 3/4" Or As Needed

## DRILLING EQUIPMENT

- AUTO DRILLER – Canrig Drill Smart

## DATA ACQUISITION

- RECORDER - EDR