

DRAWWORKS

•Commander 2000 HP AC

TRAVELING BLOCK

•500 Ton Skytop Brewster

TOP DRIVE

•Canrig 500 Ton

B.O.P EQUIPMENT

- •B.O.P W/ HANDLING SYSTEM- As per Contract
- •CLOSING UNIT 220 Gallon 6 Station
- •CHOKE MANIFOLD As per Contract

MUD SYSTEM

- •MUD PUMP #1 -Emsco FB-2200 (7.5M)
- •MUD PUMP #2 -Emsco FB-2200 (7.5M)
- •MUD TANKS 800 BBL
- •SHALE SHAKER (3) Triple King Cobra Venom

STORAGE CAPACITIES

•WATER TANKS - 500 BBL

POWER PACKAGE AND LIGHTING

- •VFD Canrig VFD
- •ENGINES (3) Cat 3512C (1500 HP) w/ Bi-Fuel

MAST AND SUBSTRUCTURE

- •MAST Superior 142' x 25' w/1,000,000# Hook
- •SUBSTRUCTURE -Box on Box 27'Hx38'x47'
- •HIGH DENSITY SELF MOVING PACKAGE X-Y Axis 600' Center of Well

AUXILIARY EQUIPMENT

- •GAS BUSTER ATMOSPHERIC
- •BOILER 150 HP
- •PUSHER HOUSE 13' X 55' Atco
- •DRYING SHAKER TANK
- •FLARE TANK Cyclone Design

TUBULARS & HANDLING

- •MECHANICAL ROUGHNECK Forum WR-80
- •POWER CATWALK Canrig Power Cat 3000
- •DRILL PIPE 5" Or As Needed
- •DRILL COLLARS 6 3/4" Or As Needed

DRILLING EQUIPMENT

•DRILLER - Canrig DrillSmart

DATA ACQUISITION

•RECORDER - EDR