

# RIG #36



## DRAWWORKS

- Commander 1500 HP AC

## TRAVELING BLOCK

- National 500 Ton

## TOP DRIVE

- Canrig 500 Ton

## B.O.P EQUIPMENT

- B.O.P W/ HANDLING SYSTEM- As Per Contract
- CLOSING UNIT - 220 Gallon 6 Station
- CHOKE MANIFOLD – As Per Contract

## MUD SYSTEM

- MUD PUMP #1 – FB-1600 (7.5M)
- MUD PUMP #2 – FB-1600 (7.5M)
- MUD TANKS – 800 BBL
- SHALE SHAKER – Triple King Cobra Venom

## STORAGE CAPACITIES

- WATER TANKS - 500 BBL

## POWER PACKAGE AND LIGHTING

- VFD – Canrig VFD
- ENGINES - (3) MTU V16 2000 w/ Bi-Fuel System

## MAST AND SUBSTRUCTURE

- MAST – 142' x 25' w/1,000,000# Hook
- SUBSTRUCTURE –Box on Box 20'Hx32'x38'  
(perpendicular to mud tanks)
- HIGH DENSITY SELF MOVING PACKAGE – 135'  
Center of Well

## AUXILIARY EQUIPMENT

- BOILER - 150 HP Superior w/ Bi-Fuel System
- PUSHER HOUSE - 13' X 55' Atco
- DRYING SHAKER TANK
- FLARE TANK – Cyclone Design

## TUBULARS & HANDLING

- MECHANICAL ROUGHNECK – B&V-80
- POWER CATWALK – Power Cat 3000 DRILL PIPE  
– 5" Or As Needed
- DRILL COLLARS –6 3/4" As Needed

## DRILLING EQUIPMENT

- DRILLER – Canrig DrillSmart

## DATA ACQUISITION

- RECORDER - EDR