

# RIG #36



## DRAWWORKS

- Commander 2000 HP AC

## TRAVELING BLOCK

- National 500 Ton

## TOP DRIVE

- Canrig 500 Ton

## B.O.P EQUIPMENT

- B.O.P W/ HANDLING SYSTEM- As Per Contract
- CLOSING UNIT - 160 Gallon
- CHOKE MANIFOLD - As Per Contract

## MUD SYSTEM

- MUD PUMP #1 - FB-1600 (7.5M)
- MUD PUMP #2 - FB-1600 (7.5M)
- MUD PUMP #2 - FB-1600 (7.5M)
- MUD TANKS - 800 BBL
- SHALE SHAKER - (3) NOV King Cobras

## STORAGE CAPACITIES

- WATER TANKS - 400 BBL

## POWER PACKAGE AND LIGHTING

- VFD - Canrig VFD
- ENGINES - (3) MTU V16 2000 (1500 HP) w/ Bi-Fuel

## MAST AND SUBSTRUCTURE

- MAST - 142' x 25' w/1,000,000# Hook
- SUBSTRUCTURE - Superior Box on Box 26'x36'
- HIGH DENSITY SELF MOVING PACKAGE - 150' Center of Well

## AUXILIARY EQUIPMENT

- GAS BUSTER ATMOSPHERIC
- BOILER - 150 HP
- PUSHER HOUSE - 12' X 48' Alta-Fab
- DRYING SHAKER TANK
- FLARE TANK - Cyclone Design

## TUBULARS & HANDLING

- MECHANICAL ROUGHNECK - B&V-80
- POWER CATWALK - Power Cat 3000
- DRILL PIPE - 5" Or As Needed
- DRILL COLLARS - 6 3/4" As Needed

## DRILLING EQUIPMENT

- DRILLER - Canrig Drill Smart

## DATA ACQUISITION

- RECORDER - EDR