

RIG #37



DRAWWORKS

- Commander 1500 HP AC

TRAVELING BLOCK

- National 500 Ton

TOP DRIVE

- Canrig 500 Ton

B.O.P EQUIPMENT

- B.O.P W/ HANDLING SYSTEM- As Per Contract
- CLOSING UNIT - 220 Gallon 6 Station
- CHOKE MANIFOLD - As Per Contract

MUD SYSTEM

- MUD PUMP #1 - FB-2200 (7.5M)
- MUD PUMP #2 - FB-2200 (7.5M)
- MUD TANKS - 800 BBL
- SHALE SHAKER - (3) Triple King Cobra Venom

STORAGE CAPACITIES

- WATER TANKS - 500 BBL

POWER PACKAGE AND LIGHTING

- VFD - Canrig VFD
- ENGINES - (3) MTU V16 4000 (2000HP) w/ Bi-Fuel

MAST AND SUBSTRUCTURE

- MAST - 142' x 25' w/1,000,000# Hook
- SUBSTRUCTURE -Box on Box 27'Hx38'x47'
- DENSITY SELF MOVING PACKAGE - X-Y Axis
600' Center of Well

AUXILIARY EQUIPMENT

- GAS BUSTER ATMOSPHERIC
- BOILER - 150 HP
- PUSHER HOUSE - 13' X 55' Atco
- DRYING SHAKER TANK
- FLARE TANK - Cyclone Design

TUBULARS & HANDLING

- MECHANICAL ROUGHNECK - B&V 80
- POWER CATWALK - Canrig Power Cat 3000
- DRILL PIPE - 5" Or As Needed
- DRILL COLLARS - 6 3/4" Or As Needed

DRILLING EQUIPMENT

- DRILLER - Canrig DrillSmart

DATA ACQUISITION

- RECORDER - EDR