

# RIG #40



## DRAWWORKS

- Canrig Commander 2000AC

## TRAVELING BLOCK

- National 500 Ton

## TOP DRIVE

- Canrig 275 Ton

## B.O.P EQUIPMENT

- B.O.P – 11"5M Shaffer & 2 Single Gates, 11"5M GK Hydril Annular
- CLOSING UNIT - 160
- CHOKE MANIFOLD – 3" 5M

## MUD SYSTEM

- MUD PUMP #1 – FB-1600 (7.5M)
- MUD PUMP #2 – FB-1600 (7.5M)
- MUD PUMP #3 – FB-1600 (7.5M)
- MUD TANKS – 800 BBL
- SHALE SHAKER – (2) Dual O'Drill Linear Shakers

## STORAGE CAPACITIES

- WATER TANKS - 400 BBL

## POWER PACKAGE AND LIGHTING

- VFD – Canrig VFD
- ENGINES - (4) MTU V16 2000

## MAST AND SUBSTRUCTURE

- MAST – 142' x 25' w/ 1,000,000# Hook
- SUBSTRUCTURE – Superior Box on Box 25'x36'
- HIGH DENSITY SELF MOVING PACKAGE – 135' Center of Well

## AUXILIARY EQUIPMENT

- GAS BUSTER ATMOSPHERIC
- BOILER - 150 HP
- PUSHER HOUSE - 12' X 48' Alta-Fab

## TUBULARS & HANDLING

- MECHANICAL ROUGHNECK – B&V 80
- POWER CATWALK – Canrig Power Cat 3000
- DRILL PIPE – 5" Or As Needed
- DRILL COLLARS – 6 3/4" Or As Needed

## DRILLING EQUIPMENT

- AUTO DRILLER - As Per Contract

## DATA ACQUISITION

- RECORDER - EDR