

RIG #40



DRAWORKS

- Canrig Commander 2000AC

TRAVELING BLOCK

- National 500 Ton

TOP DRIVE

- Canrig 500 Ton

B.O.P EQUIPMENT

- B.O.P – As Per Contract
- CLOSING UNIT - 160
- CHOKE MANIFOLD – As Per Contract

MUD SYSTEM

- MUD PUMP #1 – FB-1600 (7.5M)
- MUD PUMP #2 – FB-1600 (7.5M)
- MUD PUMP #3 – FB-1600 (7.5M)
- MUD TANKS – 800 BBL
- SHALE SHAKER – (3) Triple Swaco Mongoose Pro
- DRYING SHAKER – (3) Triple Swaco Mongoose

STORAGE CAPACITIES

- WATER TANKS - 400 BBL

POWER PACKAGE AND LIGHTING

- VFD – Canrig VFD
- ENGINES - (4) MTU V16 2000 (1500 HP)

MAST AND SUBSTRUCTURE

- MAST – 142' x 25' w/ 1,000,000# Hook
- SUBSTRUCTURE – Superior Box on Box 26'x36'
- HIGH DENSITY SELF MOVING PACKAGE – 150' Center of Well

AUXILIARY EQUIPMENT

- GAS BUSTER ATMOSPHERIC
- BOILER - 150 HP
- PUSHER HOUSE - 12' X 48' Alta-Fab

TUBULARS & HANDLING

- MECHANICAL ROUGHNECK – B&V 80
- POWER CATWALK – Canrig Power Cat 3000
- DRILL PIPE – 5" Or As Needed
- DRILL COLLARS – 6 3/4" Or As Needed

DRILLING EQUIPMENT

- AUTO DRILLER - Canrig Drill Smart

DATA ACQUISITION

- RECORDER - EDR as Per Contract