

RIG #42



DRAWWORKS

- Commander 2000AC

TRAVELING BLOCK

- Skytop Brewster 500 Ton

TOP DRIVE

- Canrig 500 Ton

B.O.P EQUIPMENT

- B.O.P W/ HANDLING SYSTEM – As Per Contract
- CLOSING UNIT – 220 Gallon 6 Station
- CHOKE MANIFOLD – As Per Contract

MUD SYSTEM

- MUD PUMP #1 –FB-2200 (7.5M)
- MUD PUMP #2 –FB-2200 (7.5M)
- MUD TANKS – 800 BBL
- SHALE SHAKER – Triple Swaco

STORAGE CAPACITIES

- WATER TANKS - 500 BBL

POWER PACKAGE AND LIGHTING

- VFD – Canrig VFD
- ENGINES - (3) MTU 16V 4000 (2000HP)

MAST AND SUBSTRUCTURE

- MAST – 142' x 25' w/1,000,000# Hook
- SUBSTRUCTURE –Box on Box 27'Hx38'x47'
- HIGH DENSITY SELF MOVING PACKAGE – X-Y Axis 600' Center of Well

AUXILIARY EQUIPMENT

- GAS BUSTER ATMOSPHERIC
- BOILER - 150 HP
- PUSHER HOUSE - 13' X 55' Atco
- DRYING SHAKER TANK – Triple Swaco
- FLARE TANK – Cyclone Design

TUBULARS & HANDLING

- MECHANICAL ROUGHNECK – B&V 80
- POWER CATWALK – Canrig Power Cat 3000
- DRILL PIPE – 5" Or As Needed
- DRILL COLLARS – 6 3/4" Or As Needed

DRILLING EQUIPMENT

- AUTO DRILLER - Canrig Drill Smart

DATA ACQUISITION

- RECORDER - EDR As Per Contract